T·Y·LIN INTERNATIONAL
engineers | planners | scientists

Chula Vista Light Rail Corridor Improvements

Project: Chula Vista Grade Separations
Location: Palomar Street
Date: 7/3/2012

ALTERNATIVES CONSIDERED		TECHNICAL EVALUATION							PASS/FAIL		
Alt	Description	Constructibility	Customer Experience	Utility Impacts	Imp. Site Efficiency	Long Term Maintenance	Enhance Ped. Movement	Imp. Comm. Acceptance	City Acceptance	<Budget?	SCORE
P1	Palomar St - Over - In Place	6	5	2	7	4	9	5	1	1	**600**
P2	Palomar St - Under - In Place	6	8	3	8	3	8	8	1	1	**676**
P3	Palomar St - Over - Road	4	4	1	5	4	10	4	1	1	**529**

EVALUATION CRITERIA DEFINITIONS								
MAJOR CRITERIA	Constructability	Customer Experience	Utility Impacts	Improve Site Efficiency	Long Term Maintenance	Enhance Ped Movement	Community Acceptance	
Weighted Score	14.3	14.3	9.5	14.3	9.5	23.8	14.3	100.0
SUB-CRITERIA								
	-	-	-	-	-	-	-	

ATTACHMENT 20