
CHULA VISTA FIRE DEPARTMENT

FIRE PREVENTION DIVISION

Exterior Strobe Detail



Strobe Specifications

- 1. Shall be weatherproof per NEMA 4X
- 2. Install at a height between 12 16 feet above finished grade
- 3. Strobe shall only be activated upon water flow.
- 4. The strobe shall be located to create a perpendicular angle with the FDC/PIV
- 5. Strobe shall be a minimum of 110cd and a strobe only device